Work items: Required

Eye protection Work boots (no sneakers or open toe shoes) Long sleeve shirt Long pants Heavy-duty work gloves Min. 12, N-95 masks Toolbox Tool belt Hammer Tape measure Pry-bar Razor knife (box knife) with extra blades Pliers Straight and Philips screwdrivers Marking pencils (extras) Ear protection- working with power tools Hardhat-for over head demolition Note pad Bottled water/drinking container

Anyone installing dry wall should have these tools: Crew leaders must make sure they have this equipment if working installing drywall

Mud pan- for spackle 4" taping knife/trowel 6"-8"-10"-12" spackling knife/trowel 4' T-square Sheet rock saw Sheet rock rasp Hand sander Pole sander Sand paper- for spackle Dust mask Eye protection Dry wall nails/screws Box (razor) knife-extra blades Min. 12' tape measure Marking pencil(s) Items to bring if you have them: Crew leaders must make sure they have the right tools for the job.

*First Aid kit
*Screw drivers-straight and Philips
*Electrical/battery powered construction tools

Electric screwdriver w/ extra bits
Saw w/ extra blades
Drill and bits

*Sledgehammer

*Heavy-duty extension cords
*Construction hand tools
Chalk line
Level
Chisels
Square
Any tool you think you might need

*Roofing nailer- air hoses- compressor